

Minnesota Department Of Transportation

Report Printed Date: 2/10/2026

Contract: 250097

Change Order No.: 0003

Net Change Order Amount: \$2,247.45

Prime Contractor: Henning Construction, Inc., 0000211235

Spec Book Year: 20

CO Type: COLevel2

Awarded Contract Amount: \$13,598,341.93

Funding Source: ON NHS

State Proj. No.: 6705-50

Resident Engineer: Brett Paasch

Fed. Proj. No.: 6726018

Admin Office: 7B-Windom

District: 7 Mankato

County: C067 ROCK

Route: T.H. 75

Reason: 1402.5 Extra Work

Location: T.H. 75 FROM WEST MAPLE STREET TO WEST VETERAN'S DRIVE IN LUVERNE.

Description: Structure 5551/5551A Modification

Explanation:

- Issue** Structures 5551 and 5551A needed to be modified to account for a drainage pond which is being built by the city of Luverne, and to adjust the size of the outlet pipe due to having the existing being a 24" instead of 36".
- Resolution** After discussion with Mn/DOT Hydraulic Engineer and the City of Luverne Engineer it was determined that modifying the structures now would eliminate the need to remove the structures in the very near future to account for the future pond. During modifications of the shop drawings it was also found to be tying into a 24" pipe and not a 36" pipe per the plan.
- Entitlement** The Engineer determined the Contract needs to be revised in accordance with MnDOT Specification 1402.5 Extra Work.
- Impact** The Contract change does not modify the contract time.
- Cost** The cost of this change is per contract unit cost and negotiated pricing.
- Payment** Payment for this change is per estimate below.

Increases/Decreases

Item Description	Item ID	Project Line	Contract Line	Project	Category	Item Source	Quantity Inc/Dec	Unit	Unit Price	Dollar Amount
CONSTRUCT DRAINAGE STRUCTURE DESIGN 96-4020	2506503/04820	00920	0700	134930	0001	Original	21.000	L F	\$2,881.90	\$60,519.90
CONSTRUCT DRAINAGE STRUCTURE DESIGN 84-4020	2506503/04220	00910	0695	134930	0001	Original	-7.000	L F	\$2,095.45	-\$14,668.15
CONSTRUCT DRAINAGE STRUCTURE DESIGN 108-4020	2506503/05420	00930	0705	134930	0001	Original	-12.000	L F	\$3,702.10	-\$44,425.20
36" RC PIPE SEWER DESIGN 3006 CLASS IV	2503503/19364	00750	0430	134930	0001	Original	-8.000	L F	\$160.50	-\$1,284.00
48" RC PIPE SEWER DESIGN 3006 CLASS III	2503503/19483	00760	0435	134930	0001	Original	8.000	L F	\$224.15	\$1,793.20
CONSTRUCT DRAINAGE STRUCTURE DESIGN F	2506503/00060	00810	0645	134930	0001	Original	-2.000	L F	\$464.15	-\$928.30
									Total:	\$1,007.45

Minnesota Department Of Transportation

Report Printed Date: 2/10/2026

New Items

Item Description	Item ID	Item Reason	Project Line	Cont. Line	Project	Category	Quantity	Unit	Unit Price	Dollar Amount
24" HDPE Dual Wall to tie to existing storm pipe. - CHANGE ORDER LIN FT	1402603/00010	PC-Neg	2470	1160	134930	0001 - SP 6705-50 (A)	8.000	L F	\$155.00	\$1,240.00
									Total:	\$1,240.00

Time Adjustments


Time ID	Time Description	Time Type	Original	Current	Adjustment	New

Project/Category Summary

Project Description	Project	Category	Category Description	Dollar Amount
GRADING, CONCRETE & BITUMINOUS SURFACING, ADA IMPROVEMENTS, SIGNAL, AND LIGHTING.	134930	0001	SP 6705-50 (A)	\$1,240.00
GRADING, CONCRETE & BITUMINOUS SURFACING, ADA IMPROVEMENTS, SIGNAL, AND LIGHTING.	134930	0001	SP 6705-50 (A)	\$1,007.45
			Net Change Order Amount:	\$2,247.45

Minnesota Department Of Transportation

Report Printed Date: 2/10/2026

	Signature & Date	
Project Engineer/Project Supervisor		2-10-2026
Contractor		2/11/2026
Commissioner of Transportation Pursuant to Delegation		
Commissioner of Administration Pursuant to Delegation		
Consultant Contract Administrator (recommendation for Approval only)		
Local Agency (if funded wholly or in part by Local Agency)	DocuSigned by:  E570AB4F8451454...	2/13/2026

ATTACHMENTS: By signing this agreement, the Contractor acknowledges receipt of the specified attachments (if applicable)